XLERATOR RECESS KIT INSTALLATION


STOCK # 40502


#630 TP Wrench (6) Mounting Nuts (4) SS Screws



FOR PROPER ELECTRICAL CONNECTIONS, CHECK YOUR LOCAL BUILDING CODES. YOUR UNIT WIRING MUST BE INSTALLED BY A QUALIFIED, LICENSED ELECTRICIAN. SEE DRYER INSTALLATION INSTRUCTIONS FOR WIRING INFORMATION.

INSTALLATION NOTE: After unpacking, remove and save the bolts holding the dryer mounting plate to the wall box.





CONSTRUCTION

Wall box is fabricated of 22 GA 18-8 type 304 stainless steel with #4 satin finish. Dryer mounting plate is fabricated of 16 GA 18-8 type 304 stainless steel. All welded construction.

OVERALL DIMENSIONS

16 3/8" wide x 26" high x 3 3/8" deep (416 mm wide x 660 mm high x 86 mm deep)

ROUGH WALL OPENING

14 1/2" wide x 24 3/8" high x 4" deep (368 mm wide x 619 mm high x 102 mm deep) **Note**: Not recommended for existing single block wall.

INSTALLATION GUIDE (CONSULT LOCAL ADA CODES)

When installed, bottom of hand dryer will be 10" (254 mm) above <u>bottom</u> of rough wall opening. Therefore, bottom of rough wall opening should be 10" (254 mm) below suggested mounting height for hand dryer. (See suggested dryer mounting heights above).









Re-fasten dryer mounting plate to Wall Box using the 2 button head tamper proof bolts previously removed.



Knock out the appropriate electrical inlet on dryer wall plate and install dryer insides onto dryer mounting plate using all 6 mounting nuts supplied.



Connect electrical service to Terminal Block of hand dryer. Properly ground the dryer via the supplied ground screw.



Remove 2 button head bolts holding dryer mounting plate to Wall Box and tilt downwards, being careful that safety chain is connected.



Install dryer cover with 2 flat head tamper proof bolts using special wrench provided.



Return dryer to upright position and refasten to Wall Box using the 2 button head tamper proof bolts. Remove protective film from Wall Box. Turn on power and test for proper operation.

